

Roofing, LLC
Residential and Commercial Roofing
150 S. Wacker Dr. Chicago, IL 60606
evogel@catholicextension.org
312-795-6095

DATE

Roofing portion- Main building

Remove existing roofing materials- stamped shingles and sheathing:
3 days per side @ \$1,700.00 per day-
6 days total- **\$10,200.00**

Re-sheet with 5/8" OSB after insulation is installed:
2 days per side @ \$1,700.00 per day
Labor- 4 days total- \$6,800.00
Materials- \$1,500.00
Total- **\$8,300.00**

Build cricket at bell tower:
Labor- \$355.00
Materials- \$125.00
Total- **\$480.00**

Roofing portion- side wings

Remove existing roofing materials- stamped shingles:
1 day @ \$1,700.00 per day
1 day total- **\$1,700.00**

Roofing portion- radius roof and turret roof

Remove existing roofing materials- standing seam metal
4 hrs. @ \$127.50
Total- **\$510.00**

Insulation portion-

Corbond bays between rafters to R40 value, Corbond dormers to highest level possible.
3" Corbond on wall behind altar and choir loft wall.
Total- **\$19,303.33**

Loose-fill fiberglass will be blown in over existing insulation for offices and hall. An R49 value will be achieved.
Total- **\$636.66**

Remove Stone Chimney

Total- **\$1,500.00**

Re-shingle portion

Install DaVinci Slate composite shingles- install on main roof, dormers, side wings and radius roofs.

43 squares total including waste. 7 1/2" exposure.

Materials- \$22,403.33

Labor-\$18,700.00

Total- **\$41,103.33**

Fir-out Choir loft wall, insulate, sheet rock and finish:

Materials- \$200.00

Labor- \$850.00

Total- **\$1,050.00**

Window coverings-

Install Lexan to gables of dormers

Materials- \$375.00

Labor- \$566.00

Total- **\$941.00**

Bell Tower portion-

Remove louvers and paint wood:

Materials- \$75.00

Labor- \$850.00

Total- **\$925.00**

Prepare and apply black roof coating to existing metal shingles on tower and radius wall.

Materials- \$750.00

Labor- \$1,700.00

Total- **\$2,450.00**

Cross portion-

Remove existing cross for inspection, refurbish if possible. Replace if needed. Reattach as required.

Materials- \$100.00

Labor- \$600.00

Total- **\$700.00**

Equipment rental-

Additional scaffolding, lifting equipment, roll-off container for disposal, etc.

\$3,000.00

**Clean-up labor-
\$1,700.00**

**Projected Project Total:
\$94,499.32**

NOTES:

This estimate is good for only 30 days, after which it will have to be reviewed. The price will be locked-in by a signed contract and 33% deposit.

If you were to choose the Lamirite Slate product offered by Tamko, Inc, as opposed to the DaVinci product, you could save approximately \$3,600.00 on materials cost. I have samples of the Tamko product coming for your inspection.